

CERTIFICATE

CERTIFIED LAND CORNER

No. 46

41801100020

I, Lawrence A. Feddersen, do hereby certify that on the 18 day of September 1981, I found ~~(evidence)~~ (no evidence) of the N $\frac{1}{4}$  corner of Section 15, T 18 N, R 1E Fourth Principal Meridian, and I re-established said corner according to the Wisconsin Statutes as shown and described hereon.

Dated this 30 day of Nov. 1981.

*Lawrence A. Feddersen*

Registered Land Surveyor  
Title

History of corner establishment since Original Government Survey

None

Description of corner evidence found:

Set Harrison half way on straight line between the Northeast corner and the Northwest corner.  
Two-way fence corner was not used as fence had many bends and used a tree as the corner. Adjacent property owners North and South, both agreed the fence was not correct.

COUNTY SURVEYOR FORM NO. 1

Description of corner and witness monuments, references and accessories used to perpetuate the original or re-established location of this corner:

Witnesses to corner location:

- Lawrence Feddersen
- Thomas Mangene
- Timothy Fisher

nail/washer in  
blaze and painted  
orange in 5 $\frac{1}{2}$ "  
double white oak



set Harrison Monument

nail/washer in  
blaze and painted  
orange in 5 $\frac{1}{2}$ " white oak

dead red oak

nail/washer in  
blaze and painted  
orange in 10" twin  
red oak

nail/washer in  
blaze and painted  
orange in 7" white  
oak



**Approved: HARLEY A. SIME**  
**MONROE CO. SURVEYOR**

SURVEY CONTROL ORDER

|            |       |
|------------|-------|
| Horizontal | _____ |
| Vertical   | _____ |

WISCONSIN COORDINATE SYSTEM

| Corner            | East (X) | North (Y) | Elevation (Z) | Zone |
|-------------------|----------|-----------|---------------|------|
| Control Sta. Name |          |           |               |      |

~~City/Village/Town~~ of Byron  
County of Monroe