

37

U.S. PUBLIC LAND CORNER MAINTENANCE

Corner ID : E1/4 Sec.9, T19N-R1W

21901092000

<u>DATE</u>	<u>CREW</u>	<u>MONUMENT TYPE</u> -----
April 23, 2014	Zachariah P. Dechant Gary L. Dechant	Existing Harrison, top broke off, 3' west of traveled centerline of CTH "N", down 16"

References:

	<u>Bearing</u>	<u>Distance</u>
1) Set 3/4"x24" hexagon iron bar, down 8"	N80E	61.28'
2) Set 3/4"x24" hexagon iron bar, down 8"	S60E	69.72'
3) Set 3/4"x24" hex iron bar, down 8", 4' NE of 8" Maple	S80W	74.03'
4) Set 3/4"x24" hex iron bar, down 6", 4' SW of 16" White Pine	N60W	92.04'

NOTE: Iron bars and Harrison set on straight lines.

COORDINATES:



CERTIFICATE

CERTIFIED LAND CORNER

No. 37

21901092000

I, Harley A. Sime, do hereby certify that on the 1st day of October 1975, I found evidence ~~(no evidence)~~ of the East 1/4 corner of Section 9, T19 N, R 1 W Fourth Principal Meridian, and I re-established said corner according to the Wisconsin Statutes as shown and described hereon.

History of original corner establishment:

O.R. Dahl, Co. Surveyor, was at this corner on Feb. 14, 1871.

Description of corner evidence found:

Found a 3/4"x24" iron bar used in previous surveys. Removed the bar and replaced it with a Harrison marker.

Dated this 1st day of March 1976.

County Surveyor _____

Approved: **HARLEY A. SIME**
MONROE CO. SURVEYOR

Description of corner and witness monuments, references and accessories used to perpetuate the original or re-established location of this corner:




Set a Harrison in the center of the road, down 1".

Witnesses to corner location:

W.C. Jung - Crew Chief *W.C. Jung*

A. Lueck

COUNTY SURVEYOR FORM NO. 1



O = LOCATION CORNER
T 19 N R 1 W
WISCONSIN

SURVEY CONTROL ORDER

Horizontal _____
Vertical _____

WISCONSIN COORDINATE SYSTEM

Corner	East (X)	North (Y)	Elevation (Z)	Zone
Control Sta. Name				

City, Village or Town Lincoln
County of Monroe