Public Involvement Handout

T of La Grange – T of Byron Forbes Road to CTH N

CTH ET, Monroe County Project ID: 7373-00-04

February 21, 2023








Existing Conditions

CTH ET Project Termini: Forbes Road to CTH N


- Project Length = 3.36 miles
- 10'-11' Driving Lanes
- 2'-3' Shoulders (0'-1' Paved)
- 2,390 Vehicles per Day (ADT 2022)
 (Forbes Road Formica Road)
- 740 Vehicles per Day (ADT 2022)
 (Formica Road CTH N)
- 10% Truck Traffic
- Major Collector
- 45 MPH Posted (Sta.13+89.89 Sta. 28+50)
- 55 MPH Statutory Speed Limit (Sta. 28+50 Sta. 191+63.10)
- Sections 25, 26 and 36, T18N, R01W,
 Town of La Grange and Sections 29, 30, 31, and 32, T18N, R01E, Town of Byron



Need for Project

- Poor Pavement Condition
- Narrow Roadway with Minimal Shoulders
- Inadequate roadside grading and vehicle recovery areas
- Inadequate Intersection Sight Distance (ISD) along CTH ET and Sideroads
- Inadequate Drainage Including Insufficient Ditching






CTH ET Segment 1: Forbes Rd – Formica Rd **Proposed Design**

- Design Class C4
- Posted Speed: 45 MPH (Sta. 13+89.89 - Sta. 28+80)
- Statutory Speed: 55 MPH (Sta. 28+80 - Sta. 63+50)
- 3,700 Vehicles per Day (ADT 2044)
- 60 MPH Design Speed

Typical Section

- 11' Driving Lanes
- 6' Shoulders (3' Paved)
- **Pavement Structure**
 - 4.25" Asphalt
 - 12" Base Aggregate Dense 1 1/4-Inch




CTH ET Segment 2: Formica Rd – CTH N

Proposed Design

- Design Class C2
- 770 Vehicles per Day (ADT 2044)
- Statutory Speed: 55 MPH
- 50 MPH Design Speed

Typical Section

- 11' Driving Lanes
- 4' Shoulders (3' Paved)
- Pavement Structure
 - 3.5" Asphalt
 - 10" Base Aggregate Dense 1 ¼-Inch



Alternate Route Map

- CTH ET will be Closed to "Thru Traffic."
- Access will be Maintained to Local Property Owners Through Construction
- Alternate Route: CTH ET USH 12 STH 21 CTH N (Approx. 10.2 miles)
- Project Duration = Approximately 6 Months of Calendar Time
- 2024 Construction

Project Schedule

Task	Description/Objective	Anticipated Date
Pavement Design Report		December 13, 2022
Safety Certification Document		December 15, 2022
Section 106 Report		January 9, 2023
Environmental Document		March 15, 2023
Transportation Management Plan		April 15, 2023
Design Study Report		May 1, 2023
Right-Of-Way Plat and Descriptions		May 15, 2023
Utility Coordination Executed		May 2023
Final (90%) Road Plans		September 1, 2023
P.S. & E. Submittal	Draft PS&E to Region Final PS&E to Central Office	September 1, 2023 November 1, 2023
Letting Date		March 12, 2024
Begin Construction		Spring 2024
End Construction		Fall 2024

CTH ET - Construction Cost Estimate

Project Cost Range

\$4,000,000 to \$4,999,999

The project is being funded (construction) through the FHWA's Federal Lands Access Program (FLAP) using Federal and Local (Monroe County) Funds.

Right-of-Way (RW) Impacts: The project will acquire RW.

- On-going project coordination with...
 - <u>Utilities</u> (Oakdale Electric Cooperative, WE Energies, Lumen (CenturyLink))
 - <u>Agencies</u> (Wis Dept. of Natural Resources, Corps of Engineers, Monroe County Zoning, Fish & Wildlife Service, Historical Societies, Native American Tribes, Dept. of Agriculture Trade and Consumer Protection, Natural Resources Conservation Service)
- Safety Improvements include...
 - Smooth roadway surface with added skid resistance, widened roadway surface to a
 consistent width with 3' paved shoulders throughout, improved roadside grading,
 centerline rumble strips, improved sight distance along CTH ET and sideroad
 intersections, superelevation improvements at horizontal curves, new traffic control
 signs, delineation and new pavement markings.

Please direction any questions to:

Ellery Schaffer, P.E. – Project Manager Jewell Associates Engineers, Inc. 560 Sunrise Drive Spring Green, WI 53588 Ph: (608) 341-8159

Email: ellery.schaffer@jewellassoc.com

Attachments:

Attachment A: Project Location Map

Attachment B: Project Overview

Attachment C: Typical Finished Sections

