


Sec. 20 T 17 R 1 W Field notes of a survey made by me, of section 20 T 17 R 1 W, April 24 1873. From E 1/4 west 40.40 ch to center which was legally established from center west 39.50 ch to W 1/4. From W 1/4 west 40 ch to NW corner. From N 1/4 S 48° 40.10 chains to center. Witness at corners  
 at center w. oak 20 S 58° 10 46 links  
 at W 1/4 on N line w. oak 24 N 74° 20 7  
 Variation of needle N 8 E courses record from true meridian  
 Witness my hand this 24th day of April 1873  
 A. S. Ingalls Co. Surveyor

Sec. 20 T 17 R 1 W Field notes of a survey of section 20 T 17 R 1 W as made by me April 25th 1873. Run from N.W. corner S 87° 10 40 1/2 chains to N 1/4. From N 1/4 S 48° 37.32 ch. to center which was legally established from W 1/4 S 89° 38 40.2 ch. to center. From center S 89° 38 40.42 chains to E 1/4. From E 1/4 south 40.19 chains to S.E. corner. From center S. 37.76 chains to S 1/4. From E 1/4 on N line S 48° 37.46 chains to E 1/4 on 1/2 line. Variation of needle N 8 E courses record from true meridian. Witness at corners established by me  
 at center w. oak 10 S 78° 10 20 links  
 at N 1/4 stake on 1/2 line w. oak 16 N 45° 10 2  
 at E 1/4 on N line w. oak 14 S 28° 8 24  
 at S 1/4 on W line B. oak 12 N 75° 8 38  
 Witness my hand this 25th day of April 1873  
 A. S. Ingalls Co. Surveyor

Sec. 7 T 16 R 2 W Field notes of a survey of Sec. 7, T. 16, R. 2, W as made by me April 27 1873. Center established at the intersection of straight 1/2 lines & stakes established at proportional distances from their respective corners on each side. From E 1/4 south 40.50 ch to S.E. corner. From S.E. corner S 89° 20 37.5 ch to S 1/4. From S 1/4 N 8° 10 40 chains to N 1/4. From N 1/4 west 40.05 ch to W corner. From W 1/4 on N line N 88° 40 chains to W 1/4 on 1/2 line. From W 1/4 on 1/2 line N 88° 40.30 ch. to W 1/4 on N line. From E 1/4 on N line south 40.27 ch to E 1/4 on 1/2 line. From E 1/4 on 1/2 line S 48° 8 40 chains to E 1/4 on N line. Witness at the corners established by me



- 1. at S 1/4 stake on W 1/2 line w. oak 10 S 48° 8 22
- 2. " W 1/4 stake on 1/2 line w. oak 12 S 17° 20 7
- 3. " E 1/4 " on N line B. oak 16 S 75° 8 54
- 4. " E 1/4 " on S 1/2 line w. oak 10 N 85° 10 46
- 5. " E 1/4 " on 1/2 line w. oak 14 N 60° 20 28
- 6. " E 1/4 " on N 1/2 line B. oak 16 N 52° 10 12

Witness my hand this 27th day of April 1873  
 A. S. Ingalls Co. Surveyor