

Resurvey of a part of Sec 31, Town 15 Range 2 West made the 15<sup>th</sup> & 16<sup>th</sup> days of March 1895 and proceeded as follows. Commenced at the North 1/4 post, being a known corner, with one original Metrop tree described as a White Oak C. S 72° E 260 Links


Set compass on 4° E. run south and set temporary 1/8, 1/4 1/8 stakes and intersected south line at known 1/4 post, a large stake surrounded by stones. Said 1/4 corner has known and recognized by old being settled for over thirty years. Metrop trees gone, but new described and location pointed out by Mr Stoddard and others

My measurement fell short 30 1/2 links

Retraced 1/4 line setting 1/8 and 1/4 posts at their proportionate distances. Then went to where it was claimed that the 1/4 post stood, in West side of said section, found Metrop trees gone, as well as stake but by digging down at place supposed to be the corner found a round hole 4 in. in diameter with bits of rotted wood.

Set post in hole run East variation and struck Center 1/4 post, thence East on same variation to old 1/8 post, intersecting at 1/4 corner on E side of section. Returned to S 1/4 post run East set 1/4 post thence East 20 rods at to corner of Olson & Stoddard, thence to corner to S E corner of section 31 for further particulars see diagram below. The chain used was a Standard 50 foot Engineers Chain

Chained by Stephen Stoddard and Johnson run duly sworn



- Metrop at NW Oak C S 72° E 260 Links
- " " (2) Jack " 8 72° E 24 "
- " " 1/4 Brw " 12 S 58 1/2 W 126 "
- " " 3 " " 15 N 84° E 84 "