

41501200020

I, William C. Jung, do hereby certify that on the twenty-second day of March 1982 I found (evidence) of the North 1/4 corner of Section 29, T 15 N, R 1 E Fourth Principal Meridian, and I re-established said corner according to the Wisconsin Statutes as shown and described hereon.

Dated this 29th day of Mar. 1982.

William C. Jung, R.L.S. 1323

County Surveyor's Office
Title

William C. Jung

Description of corner and witness monuments, references and accessories used to perpetuate the original or re-established location of this corner:

Witnesses to corner location:

Gary Dechant

Bryan Meyer

COUNTY SURVEYOR FORM NO. 1


**Approved: HARLEY A. SIME
MONROE CO. SURVEYOR**

History of corner establishment since Original Government Survey


No recorded history since the Original Gov't. Survey.

Description of corner evidence found:

I accepted a four-way occupied fence corner as the best available evidence of the Original Gov't Corner. In addition, according to the original notes, this corner should be 1422' West of the creek, and I measure 1414'+. Considering a culvert was put in, this fits good. I also fit an old Westerly fence at the latter point mentioned.



NOTE: All trees are double blazed. They are also hacked in the side with a nail set in the hack. Distances are measured direct from corner to nails. Trees are also scribed.



O = LOCATION CORNER

T 15 N R 1 E

WISCONSIN

SURVEY CONTROL ORDER

Horizontal	_____
Vertical	_____

WISCONSIN COORDINATE SYSTEM

Corner	East (X)	North (Y)	Elevation (Z)	Zone
Control Sta. Name				

~~City, Village or~~ Town of Glendale
County of Monroe

