

21501232000

I, William C. Jung, do hereby certify that on the 20th day of September 1982, I found (evidence) ~~(no evidence)~~ of the West 1/4 corner of Section 24, T 15 N, R 1 W Fourth Principal Meridian, and I re-established said corner according to the Wisconsin Statutes as shown and described hereon.

History of corner establishment since Original Government Survey

LaRue re-established this corner in April of 1900. Holden found the original corner in June of 1910.

Description of corner evidence found:

I accepted the occupied fence corner as the best available evidence of the original government corner. This location fits the existing fences at the Center 1/4 and East 1/4 very well. Also, with my final 1/2 mile along the West line-SW1/4-Section 24, I find that I measure 1332'+ South to the W1/16SW occupied fence corner and I compute 1332.76' (LaRue had about 1327.75') to the true corner.

Dated this 27th day of Jan. 1983.

William C. Jung

Deputy County Surveyor

Title


COUNTY SURVEYOR FORM NO. 1

Description of corner and witness monuments, references and accessories used to perpetuate the original or re-established location of this corner:

Witnesses to corner location:

William C. Jung

Melvin Pliner




SURVEY CONTROL ORDER

Horizontal	_____
Vertical	_____


Set Harrison, 5" West of post

Set 3/4"x24" I.B. →

Both B.T.'s are double blazed; each dist. is to a nail in a hack on the side of the tree.



Approved: **HARLEY A. SIME**  
**MONROE CO. SURVEYOR**



WISCONSIN COORDINATE SYSTEM

Corner	East (X)	North (Y)	Elevation (Z)	Zone
Control Sta. Name				

~~City, Village or~~ Town of Wellington

County of Monroe